



DEEPAK FERTILISERS
AND PETROCHEMICALS
CORPORATION LIMITED

DEEPAK FERTILISERS AND PETROCHEMICALS CORPORATION LTD. (DFPCL/ Company)

Registered Office: –Sai Hira, Survey no. 93, Mundhwa, Pune – 411036, Maharashtra

Works at: PLOT K1, MIDC INDUSTRIAL AREA, TALOJA DIST : RAIGAD

Tender for value base Annual rate Contract for Civil Jobs at our plant at MIDC, Taloja

Tender Ref.: 163/ 2019 Date: 27.12.2019

Technical bids are invited in Sealed Envelope with EMD. The sealed envelope shall be super scribed with Tender Reference Number, Name of Work & content in it and addressed to Mr. Rajesh Shankaratti , Deepak Fertilisers And Petrochemicals Corporation Ltd. at Plot K – 1 MIDC Industrial Area, Taloja, 410 208, Dist. : RAIGAD

Stage I Bidding

- Sealed Envelop –I_: General Terms and Conditions, Commercial Terms and Conditions Special Conditions and Scope of work (Excluding Price Bid).

Exceptions and deviations, which Tenderer may desire to stipulate. (Tenderers are advised to submit the Tender strictly on the terms and conditions of the contract and specifications contained in the Tender documents and not to stipulate any deviations. However, if deviations become unavoidable, then it may be stipulated. The Company/ DFPCL reserve the right to reject such deviations or evaluate the Tenderers containing deviations having financial implication, by adding the cost for such deviations as may be determined by the Company/ DFPCL).

Stage II Bidding

Tenderer will submit the price bid online through the platform provided by DFPCL service provider Ariba system.

Submission & opening of the Bid: The Bidders shall submit the duly filled in all the bid documents (Stage I) signing on each page & every component by the authorized signatory & send the documents to Purchase Department latest by 10.01.2020

All the above documents should be handed over to Mr Rajesh Shankaratti (Sr. Manager Purchase) Phone: 022-67684116 representative of DFPCL.

E reverse Auction:

After submission of Stage I bid documents and online price bid E auction will be conducted. The E auction will be governed by the Business Rules for Reverse Auction as per enclosed pages in Stage I bidding.

Technically acceptable Tenderers against the tender can only participate in further process.

The Tenderers who do not fulfill all or any of the conditions laid down in the tender document are liable to be ignored at the sole discretion of DFPCL. DFPCL also reserves the right to reject any/all the offers without assigning any reason thereof.

In case of any Technical queries you may contact our Job Controller Shri Manish Pandit – 022 50684461 . For commercial queries you may contact Mr Rajesh Shankaratti Tel No 022 50684116

Thanking you,

Yours faithfully,

For Deepak Fertilisers And Petrochemicals Corporation Limited

Srikanta Behera

General Manager (Commercial)

INDEX

Sr No	Description	Page No
1	General Terms and Conditions	5
2	Special Terms and Conditions	12
3	Scope of work / Price Bid Format	25
4	Commercial Terms and Conditions	62

The following are Prequalification Criteria to be submitted along with Stage 1 bidding:

1. Contractor has carried out similar type of Civil maintenance activities in past. PO copies of recent similar job to be submitted.
2. 3 to 5 years experience in similar field.
3. Number of Permanent Manpower list
4. List of clients of the contractor
5. Proof of Annual Turnover of Rs. 1 Crores
6. Compliances of statutory requirement like registration under ESIC, PF and Other related statutory Acts, Rules and Regulations prevailing for the purpose of implementation of the contract.
7. Able to deploy sufficient and competent manpower as per requirement (Min 20)

ANNEXURE I

1.0 GENERAL TERMS AND CONDITIONS FOR TENDER SUBMISSION:-

A. Earnest Money Deposit of Rs.50,000/- in the form of Bank demand draft will have to be submitted in favour of Deepak Fertilisers And Petrochemicals Corporation Ltd, payable at Mumbai, drawn on any nationalized bank or any reputed private banks, like IDBI, Axis Bank, etc. The same should be submitted along with Technical Bid. The Earnest Money Deposit will not carry any interest. Tenders received without EMD will be disqualified.

B. All pages of the tender form and questionnaire must be signed and sealed by Tenderers.

C. Tenderers have to submit details along with documentary evidences for the following :

1] Registration certificate as Proprietary/partnership firm/private ltd or Public ltd Company.

2] Registration certificate with PF organization for allotment of PF code number.

3] Registration certificate with GST for allotment of GST number.

4] Allotment letter under ESIC Act

5] Registration certificate under Maharashtra Labor Welfare Board.

6] Registration certificate for professional Tax.

7] Registration certificate under Maharashtra Labor Welfare Board.

8] Registration certificate with Income Tax Dept for allotment of permanent income tax code number.

9] Tenderers are advised to submit their bids strictly on the terms and conditions of the bid document and not to stipulate any deviation.

10] ISO Certification holder : Name of certification: -----Validity : ----- (Attested Copy to be enclosed)

11] Organization Chart : Executive ----- , Technical Staff----- (Attested Copy to be Enclosed giving the details)

12] List of requisite machinery, tools & tackles, equipment. (Attested Copy to be enclosed)

13] Audited annual Turn over: for last three Financial Years.

14] List of similar jobs carried out in other company.

15] Client List

Special Note : The contractors who are registered with DFPCL need not to submit the documents mentioned above.

- D. DFPCL reserves the right to accept or reject any or all tenders at its sole discretion without assigning any reason.
- E. Late tender will not be accepted / received.
- F. Canvassing in any connection with the tender in any form is strictly prohibited. Tenderers who resort to canvassing will be liable for rejection and EMD will be forfeited of EMD
- G. In case of any unscheduled holiday falling on the prescribed closing or opening day of the tender, the next working day will be treated as scheduled for opening or closing day of the tender as the case may be.
- H. The bidders are advised to read carefully all the terms and conditions of the tender document which will form part of the contract. Tenderers are advised to submit their bids strictly on the terms and conditions of the bid document and not to stipulate any deviation.
- I. If the Tenderers give wrong information deliberately to create conditions for acceptance of the tender, the DFPCL reserves the right to reject such tenders without assigning any reason.
- J. Not more than one tender will be submitted by one Tenderer for the same work.
- K. Not more than one tender will be submitted by one Tenderer for the same work.

2.0 INSTRUCTIONS FOR SUBMISSION OF TENDER :

- (i) The Tenderers are advised to visit the site of work to acquaint themselves as to the nature and location of the work, access to the site, the general & local conditions, particularly those bearing upon transportation, disposal, handling and storage of materials, availability of labour, water, electric power, physical conditions etc. and shall be included on such account while quoting for the tender.
- (ii) Tenderers shall quote the tender in the prescribed format of the tender document. Tenders should be free from overwriting. All corrections should be duly attested by the tenderer. Tenders should be signed by person/s that are legally authorized to sign on behalf of the person or firm or company tendering and in case of firm / company tender should bear its seal or stamp.
- (iii) Tender format should contain columns for amount in Rupees (if any),
- (iv) The Tenderers shall not stipulate any additional conditions. Any tender containing such conditions will be summarily rejected.
- (v) The work will be split up between two or more Contractors or accepted in part and not in entirety, if considered expedient at the sole discretion of DFPCL Management.

- (vi) Submission of a tender will be conclusive evidence to the fact that the Tenderer has fully satisfied himself as to the nature and scope of work to be done, procedures for issue or materials, conditions of contract,, local precautions to be ensured, security rules to be followed and all other factors affecting the performance of the contract and the cost thereof.
- (vii) It will be obligatory on the part of Tenderers to sign the documents for all the component part on each and every page.
- (viii) No Bidder is allowed to bid below the current minimum wages applicable.

3.0 AMENDMENT TO NIT (Notice Inviting Tender)

At any time prior to the deadline for submission of bids, DFPCL or its nominee or its consultants may for any reason, whether at its own initiative or otherwise or in response to any clarification requested by a prospective Bidder, modify the NIT by amendment. The amendment will be notified in writing to all prospective Bidders who have received the NIT and the amendment will be binding on them. To afford prospective Bidders reasonable time to take the amendment into account in preparing their tenders, extension of time as may be reasonable, will be given for submission of tenders.

4.0 SUBMISSION OF TENDERS:

The Bidder shall bear all costs associated with the preparation and submission of Bid and neither the company nor its nominee nor its consultants will be responsible or liable for these costs, regardless of the conduct or outcome of the bidding process. Any clarification required by prospective bidder shall be furnished in writing soon after its receipt so as to ensure submission of bid on or before bid closing date. Metric measurement system shall be applied, wherever it is applicable.

5.0 EARNEST MONEY DEOSIT (EMD)

The amount of earnest Money shall be deposited in the form of Demand Draft- The EMD should be in the name of Deepak Fertilisers And Petrochemicals Corporation- Ltd. payable at Mumbai drawn on any nationalized Bank or reputed private bank. The EMD will be forfeited in the event of the Contractor failing to commence the work within a 30 days period. The Earnest money deposited [E.M.D.] by the successful Tenderer's shall be Returned to the bidder after the commencement of the work and receipt of bank guarantee towards security deposit. The tenders without E.M.D. shall be liable for rejection. If for any reason the bidder withdraws his bid at any time prior to expiry of the

validity period or refuses to execute the work after issue of the letter of intent/Work Order, the amount of Earnest Money is liable to be forfeited. Earnest Money Deposit will not carry interest. E.M.D. of the unsuccessful participated bidders will be refunded with- in one month.

6.0 RIGHT OF ACCEPTANCE & REJECTION OF TENDER:

DFPCL reserves the right to accept at their sole discretion any tender in whole or part or split the work among two or more Contractors or reject any or all Bids without assigning any reason thereof. No claim for compensation etc. whatsoever will be entertained by DFPCL. If a Contractor whose past performance has not been found satisfactory in the opinion of DFPCL, then DFPCL reserves the right to refuse the tender documents or reject the tender while opening or evaluating the tenders. The decision of DFPCL regarding performance evaluation shall be final & binding on the Contractors.

7.0 VALIDITY OF BIDS:

Bids shall be valid for at least 90 days after the date of price bid opening prescribed by the DFPCL. A bid valid for a shorter period may be rejected at the discretion of DFPCL. In exceptional circumstances, DFPCL may solicit the bidder's consent to an extension of the period of validity. The request and responses thereto shall be made in writing. The bids shall be suitably extended where it is necessary at the request of DFPCL. Where bidder is unwillingly to extend the validity period, his bid shall be deemed to be invalid and the EMD would be returned to the bidder. No bidder shall be permitted to modify his bid, after commercial bids have been opened unless asked by DFPCL due to change in specifications / scope or otherwise. The Final concluding bid shall be valid for 6 months from date of auction and if any new requirement received shall be catered at same auction price.

8.0 Procedure for Reverse Auctioning

8.1 a. Reverse Auction: DFPCL will declare its **Opening Price (OP)**, which shall be displayed to all Tenderers during the start of the Reverse Auction. The Tenderer will be required to start bidding after announcement of Opening Price and decrement amount. Opening Price displayed on screen is evaluated price to DFPCL for all the items mentioned in price bid. The first online bid and the subsequent bids, received in the system during the event shall be less than the Auction's opening bid price by one decrement or multiples of decrement.

b. Reverse Auction shall be for a period of 60 minutes or as per DFPCL requirement. If a Tenderer places a bid in the last 3 **minutes** of closing of the Reverse Auction and if that bid gets accepted, then the auction's duration shall get extended automatically for another 3 **minutes**, for the entire auction (i.e. for all the items in the auction), from the time that bid comes in. The auto-extension will take place only if a bid is received & accepted in those last 3 **minutes**. If the bid does not get accepted, the auto-extension will not take place. In case, there is no bid in the last 3 **minutes** of closing of Reverse Auction, the auction shall get closed automatically without any extension. **However, Tenderers are advised not to wait till the last minute or last few seconds to enter their bid during the auto-extension period to avoid complications related with internet connectivity, network problems, system crash down, power failure, etc.**

c. After the completion of Reverse Auction, the **Closing / Final Price (CP)** shall be available on auction screen.

d. At the end of the reverse auction, L1 Tenderer (i.e. Tenderer who has quoted lowest final closing price) has to immediately provide price confirmation through email or fax on Tenderers letter-head.

8.2 During Reverse Auction, if no bid is received within the specified time, DFPCL, at its sole discretion, may decide to reschedule / scrap the Reverse Auction process / proceed with conventional mode of tendering / or finalize the tender based on Prices Bid submitted in the envelope

8.3 Placement of order on the conclusion of Reverse Auction shall be at the discretion of DFPCL. Bids once made by Tenderer, cannot be cancelled or withdrawn. If bidder withdraws the bid then the EMD of the bidder will be forfeited.

8.4 It shall be the prerogative of DFPCL to offer the Final / Closing Price of Reverse Auction to the other bidders for matching in case DFPCL decides to have more than one supplier.

8.5 The Tenderer shall be assigned a **link** by DFPCL'S Service provider.

8.6. The Tenderer will be able to view the following on screen along with the necessary fields in the Reverse Auction:

Leading Bid in the Auction (Current Lowest Rate)

Opening Price & Decrement Value.

9. DFPCL'S decision for award of Contract shall be final and binding on all the Tenderers.

10. DFPCL shall not have any liability to Tenderers for any interruption or delay in access to the site irrespective of the cause.

11. DFPCL's decision for award of contract shall be final and binding on all the tenderers.

12. SUBMISSION OF TENDERS:

The Bidder shall bear all costs associated with the preparation and submission of Bid and neither the company nor its nominee nor its consultants will be responsible or liable for these costs, regardless of the conduct or outcome of the bidding process. Any clarification required by prospective bidder shall be furnished in writing soon after its receipt so as to ensure submission of bid on or before bid closing date. Metric measurement system shall be applied, wherever it is applicable

13. RIGHT OF ACCEPTANCE & REJECTION OF TENDER:

DFPCL reserves the right to accept at their sole discretion any tender in whole or part or split the work among two or more Contractors or reject any or all Bids without assigning any reason thereof. No claim for compensation etc. whatsoever will be entertained by DFPCL. If a Tenderer/ Contractor whose past performance has not been found satisfactory in the opinion of DFPCL, then DFPCL reserves the right to refuse the tender documents or reject the tender while opening or evaluating the tenders. The decision of DFPCL regarding performance evaluation shall be final & binding on the Tenderer/ Contractors.

BUSINESS RULES FOR ONLINE PRICE BIDDING CUM REVERSE AUCTIONS

A) General Terms and conditions of Online Price Bidding cum Reverse Auction.

1. For proposed only price bidding cum reverse auction, techno commercially acceptable bidder only shall be eligible to participate.
2. DFPCL will engage the services of a service provider who will provide all necessary training and assistance before commencement of on line price bidding on Internet. Service provider shall also explain to the bidders, all the rules related to the online price bidding cum Reverse Auction / Business Rules.
3. Business rules like event date, time, bid decrement, extensions, etc. also will be communicated through service provider.

4. Vendors have to fax / email the compliance form in the prescribed (provided by service provider) before start of Online price bidding. Without this the vendor will not be eligible to participate in the event.
5. Online price bidding cum Reverse Auction will be conducted on schedule date and time.

B) Business Rule for finalization of the Online price Bidding cum Reverse Auction.

DFPCL has made arrangement with M/s. Ariba, who shall be DFPCL's authorized service provider for the same. Please go through the guidelines given below and submit your acceptance to the same.

1. Online price bidding cum reverse auction shall be conducted by DFPCL, on pre-specified date, while the vendors shall be quoting from their own offices / places of their choice. Internet connectivity shall have to be ensured by vendors themselves. In extreme case of failure of Internet connectivity, (due to any reason whatsoever may be) it is the bidders responsibility / decision to send fax / email communication immediately to M/s. DFPCL furnishing the price the bidder wants to bid on line with a request to the service provider to upload the faxed price on line so that the service provider will upload that price on line on behalf of the Bidder. It shall be noted clearly that the concerned bidder communicating this price to service provider has solely ensure that the fax message is received by the service provider has to solely ensure that the fax message is received by the service provider in a readable / legible form and also the Bidder should simultaneously check up with service provider about the clear receipt of the price faxed. It shall also be clearly understood that the bidder shall be at liberty to send such fax communications of prices to be up loaded by the service provider only within the closure of Bid time and under no circumstance it shall be allowed beyond the closure of Bid time / reverse auction. It shall also be noted that the service provider should be given a reasonable required time by the bidder, to upload such prices online and if such required time is not available at the disposal of the service provider at the time of receipt of the fax message from the bidder, the service provider will not be uploading the prices and either DFPCL or the service provider are not responsible for this unforeseen circumstances. In order to ward-off such contingent situation bidders are requested to make all the necessary arrangement/ alternatives whatever required so that they are able to circumvent such situation and still be able to participate in the online price bidding cum reverse auction successfully. Failure of

power at the premises of vendors during the online price bidding cum Reverse Auction cannot be the cause for not participating in the online bidding auction. On account of this, the time for the auction cannot be extended and neither DFPCL nor M/s. Ariba is responsible for such eventualities.

2. Those vendors who have participated in the initial online Price Bid Auction, will only be eligible to participate in the subsequent reverse auction

ANNEXURE II

Special Terms and Conditions: -

1. SAFETY ASPECTS:

1.01 Contractor to provide safety appliances like dust masks, ear plugs, Full body harness, ladder, safety shoes, helmet, hand gloves, safety goggles, PPE, rain gears, Boiler suit/overall made up from cotton cloths etc. to their personnel working inside the Complex at his cost and should adhere to safety codes as given in General Conditions of the contract.

Penalty for violation of Safety norms: Rs 500 for first instance per person, in multiple for next violation.

1. The manpower shall be confirmed physically fit by Factory Medical Officer to carry out assigned job at DFPCL work site. Contractor has to report with manpower to factory medical officer on very first day of his contract or worker first day of his duty.
2. No young, minor Child and Female labour shall be allowed to enter and work at site of DFPCL.
3. The Contractor shall ensure the safety training of their workman prior to start of the job with the help of DFPCL Supervisor and Safety Officer.
4. Electrical hand tools, welding machines deployed for the job shall be confirmed for proper earthing. The same shall be inspected by DFPCL Safety Officer and Electrical department
5. Contractor shall deploy Safety Supervisor for the contracts valuing more than 50 lacs Per annum.
6. DFPCL work site is "tobacco free site" No workers, supervisors will be carrying , storing or consuming any tobacco product. Smoking is strictly prohibited in the premises.
7. No lighting material match box, lighter, cigarates, electronic equipments shall be allowed inside factory.

8 Electronic equipments like mobile, cameras are not allowed to bring and use inside the factory. They can deposit their belongings at gate.

1.02 Safety Training

- 1) Contractor has to deploy experienced trained and skilled manpower for the job assigned.
- 2) Safety training will be given by DFPCL Safety officer to all manpower reported on duty. Contract supervisor shall prepare job safety analysis with the help of Maintenance Officer for the job to be carried out and the procedure which is going to be used for the job. On the basis of agreed procedure safety training will be given and adequacy of safety PPE's will be checked by Safety Officer.
- 3) Safety training certificate will be issued to all contractors workers. Every contractors workers will maintain safety certificate copy with him for the period of work inside the factory/ work site of DFPCL. The certificate will be valid for a period of six months from date of issue. After the validity is over, contractor and contract worker has to revalidate the certificate by acquiring additional certificate training from the Company.
- 4) Worker shall be aware of first Aid and using first Aid equipment and emergency procedures and assembly point at site.

1.03 Accidental Reporting

- 1) Safety of the worker is essence of the contract.
- 2) Any unsafe condition noticed by the Contractor/ Contract worker shall be notified to the DFPCL Supervisor and Safety officer.
- 3) Any near miss, accident minor injury , first aid or major injury shall be reported to OHC & safety officer in written by contractor within four hours with cause of incident.
- 4) First Aid treatment shall be made available at OHC. Any more treatment advised by OHC /Factory medical officer shall be made available by contractor at ESIC recognized hospital/specialized hospital. It is sole responsibility of contractor to make available in time best treatment to the worker at his cost/insurance. DFPCL shall not be responsible for the same.

1.04 Safety performance

- 1) Every contract shall be vetted for safety performance of previous contract and experience
- 2) Safety training to workers, proactive performance, availability of safety appliances, Attitude towards safety implementation, rewards to the worker will be evaluation parameters.

2. Labour law and Safety codes:

All the matters concerned with labour management shall be as per the Labour laws. Contractor will obtain labour license on arrival at site before commencement of the job. The first RA bill shall be released only on submission of a copy of labour license duly attested by DFPCL Administration in the prescribed format. If labour license is not applicable, the contractor shall obtain a confirmation to this effect from DFPCL Administration.

Contractor will comply with all labor and other statutory laws applicable from time to time. All labour laws, such as Contract Labour (Regulation and Abolition) Act 1970 with Maharashtra and Central Rules, Employees State Insurance Act with Rules & Regulations, The Maharashtra Workmen's Minimum House Rent Allowance Act, 1983 with Rules 1990, The Payment of Bonus Act, 1965 with Rules 1975, Factories Act with Mah. Rules, The Employees Provident Funds and Miscellaneous Provisions Act, 1952, Minimum Wages Act 1948, Payment of Wages Act 1936, Maharashtra Labour Welfare Act, etc. and such other acts which are in force or which may come in force during the subsisting of the contract should be adhered by the Tenderer/ Contractor and such other rules/ regulations/ laws made applicable from time to time.

The Contractor shall be solely responsible for its employees. And always keep the DFPCL Indemnified from all losses, actions, penalties etc arising out of this Tender/ Contract.

2.1 Deployment of Medically Fit Manpower:

For the due execution of this Contract, the Contractor shall deploy workers/supervisors who are at all times physically and mentally fit and are not disabled/handicapped and do not suffer from any chronic or contagious disease. It shall be the responsibility of the contractor to ensure that its Workers/Supervisors employed are medically fit. The Contractor shall give a written declaration as regards the fitness of the Workers/Supervisors employed at the time of applying for the Gate Pass. If any employee employed by the Contractor becomes or is declared medically unfit after the issuance of the Gate Pass, the DFPCL shall revoke the Gate Pass.

Failure to comply with this stipulation shall entail penalty as may be decided by the management apart from refusing entry to such Workers/Supervisors of the contractor. The decision of the DFPCL's Medical Officer in this regard shall be final.

2.2 MEDICAL EXAMINATION:

2.2.1 Contractor should ensure that all its Workers/Supervisors deployed at DFPCL sites undergo pre employment fitness examination. The form No.33 (Prescribed under Rule 68T & 102) should be filled up for all its Workers/Supervisors deployed and should be submitted by Him/her to user department.

2.2.2 Contract Workers/Supervisors completing 12 months shall undergo annual medical examination. Such examination must include the following tests:-

- 1) Complete Physical Examination.
- 2) X-Ray chest PA view (Once in Pre-employment then once every three years)
- 3) Complete haemogram (T&D, Hb at minimum)
- 4) One urine examination using .Multistix.

2.2.3 All entries pertaining to the periodical examination must be made and maintained in form 32 (Bounded register) prescribed under Rule 68 T & 102.

Form No.32 must be maintained in bounded register & should be submitted to the OCCUPATIONAL HEALTH CENTER for records annually.

2.2.4 Health

It is the responsibility of the vendor to provide hospitalization expenses, to carry the injured or sick personnel on duty to the designated hospital and to pay salary as per statutory requirements in case of absence from duty after suffering from occupational injury and to take post-hospitalization care with salary paid till the injured joins back duty / resigns / retires.

2.2.5 To provide documented proof for providing medical care / hospitalization, bearing hospital expenses, salary paid during and post hospitalization till complete recovery / not recovery - to Occupational Health Center.

2.2.6 To provide Fitness certificate from the hospital at the time of joining duty after suffering from occupational injury while on duty - to Occupational Health Center
To provide Unfit certificate from the Hospital as the case may be – to Occupational Health Center

2.2.7 The vendor should provide following details to Occupational Health Centre on the first day of beginning of contractual period.

1. Name with phone number/s of the manpower
2. Name of the close relative/s of the manpower with phone number/s
3. Residential address of the manpower
4. Name of the Registered / Tie-up Hospital with phone number and Doctor's name/s – wherein the manpower provided needs to be hospitalised if required.

2.3 UNIFORM:

The contractor staff shall wear uniform made up of cotton, Boiler suite, Rainy wear (During monsoon) while working inside plant premises. They shall also wear badge/name plate while they are working at site. All labour laws/ regulations shall be strictly followed by contractor as per central/state govt. directives. Before executing the contract agreement, Contractor will ensure with DFPCL P&A dept. that they are maintaining necessary records as required under labour laws.

Please note - Penalty for violation for Not wearing uniform/Boiler suit/Rainy Wear : Rs 500 for first instance per person, in multiple for next similar violations.

(A) DOCUMENTS REQUIRED AT THE TIME OF ISSUANCE OF GATE PASSES:

Whenever the contractor applies for gate passes to his worker/s to enter into DFPCL premises. They have to apply on its letter head (Format with HR Department) along-with following documents. The application should be recommended by authorized User Dept.

1. Copy of Work Order issued by DFPCL
2. Copy of Temporary or Regular ESIC Card of each worker (under ESIC Act) **or** Employees Compensation Policy (If contract worker drawing wages more than Rs.15000/-, required authentic proof i.e. appointment letter or last month payslip) or Group Personal Accident Policy along-with list of employees who is covered under the said GPA.
3. In case more than 19 persons are to be engaged, contractor has to apply and obtain Labour License under Contract Labour (R&A) Act from the State Labour authorities.
4. Copy of Allotment letter under ESIC Act
5. Copy of Registration certificate with PF organization for allotment of PF code number along with PF annual return submitted with the concern PF Commissioner.
6. Copy of Registration certificate under Maharashtra Labor Welfare Board.
7. Copy of Registration certificate for professional Tax.
8. Copy of Register of workmen employed by contractor (Form XIII) – Rule 74
9. Copy of Employment Card (Form XIV) - Rule 76
10. Copy of Application for employment, appointment letter issued by contractor to his workers.

11. Copy of Insurance coverage act covering DFPCL, as work place, and for the no. of persons to be deployed. The nature of work in the policy should be the same as per the work order issued by DFPCL.
12. Medical Examination and fitness reports in respect of all the contract labours from the designated/specified medical officers.
13. Safety training completion certificate valid for the date.(validity of certificate – six months from the date of training).

If the job is subcontracted then no objection certificate from Contract Cell of DFPCL regarding subcontracting the work/ work order issued to subcontractor by the main contractor and all the documents mentioned at Sr. No.1 to 12 are also required in respect of the subcontractor.

(B) Procedure to be followed by the contractors during the work period & documents / Registers / Challans are to be maintaining & photo copies of the same should be submitted to HR Department for verification on monthly basis on or before 28th of every month.

- 1) Wage disbursement: Minimum wages as notified by State Govt. from time to time are required to paid to the workers.
- 2) Monthly wage to all contract labours as per their actual attendance to be paid on or before 7th Day of every month in presence of authorized person from DFPCL. Wage slip to all contractors labours are to be issued during the disbursement of wages.
- 3) PF is required to be deducted in respect of all the contract labors and deposited with PF authorities by 15th Day of the month and receipt of the same to be submitted with DFPCL.
- 4) ESIC is required to be deducted in respect of all the contract labours and deposited with concern authorities by 21st day of the month and receipt of the same to be submitted with DFPCL.
- 5) Labour Welfare Fund is required to be deducted in respect of all the contract labours and deposited with concern authorities for the wages of June & December of every year within stipulated time and receipt of the same to be submitted with DFPCL.
- 6) Professional Tax is required to be deducted in respect of all the contract labours and deposited with concern authorities as per act and receipt of the same to be submitted with DFPCL.
- 7) Following records under Contract Labour (R&A) Act & other acts will also be verified by Contract Labour Cell:

1. Wage Register in form XVII. (under the C.L Act)

2. Muster Roll in Form XVI (under the C.L Act)
3. Register of deductions (under the C.L Act)
4. Register of Overtime (under the C.L Act)
5. Register of Fines (under the C.L Act)
6. Register of advances (under the C.L Act)
7. Bonus Register in Form C (under the Payment of Bonus Act)
8. Leave register in form 20 (under the Factories Act)

8) Copy of all the work orders (first two pages only -applicable only if not submitted earlier) for which clearance certificate is sought for.

9) Copy of Monthly Wage Register.

10) Copy of monthly PF challan along with receipted copy of monthly PF returns i.e. Form 12A, Form 5 and Form 10.

11) Site wise breakup of PF: If contractor is working for various other companies then the site wise breakup of Monthly PF challan/returns.

12) Copy of Labour License (if not submitted earlier).

13) In case work period is February/March, then the receipted copy of Annual PF return for that year is required.

14) Inspection report of PF and Labour authority.

Contractor should ensure that, he has complied all statutory compliances as per above said acts for that particular Month before raising wage bill. DFPCL has right to hold the bill for any particular month if the Contractor has not complied with the mandatory statutory compliances.

(D) HOUSEKEEPING:-

Contractor shall do housekeeping and shall remove all unwanted materials from the work site immediately after completion of work. Housekeeping shall also be done in between the work to keep the work area clean & tidy. 25% of bill value will be deducted if housekeeping is not done properly. Use of water shall be done economically and will not waste or drain unnecessarily. Use of water shall be done economically and will not waste or drain unnecessarily.

(E) ASSIGNMENT OR SUB-LETTING OF CONTRACT:

The Contractor shall not assign or sub-let the Contract or any part thereof or allow any person to become interested therein in any manner whatsoever without the previous consent in writing of DFPCL. Any breach of this condition shall entitle DFPCL to take such steps as may be necessary and

also terminate Contract. Such termination shall also render the Contractor liable for payment to DFPCL in respect of any loss or damage arising or ensuing from such cancellation. The permitted subletting or work by the Contractor shall not establish any contractual relationship between the sub-contractor and DFPCL and shall not release the Contractor of any responsibility under the Contract.

(F) CONTRACTOR TO BE LIABLE FOR ALL THE TAXES ETC.-

The Contractor shall be liable to pay all the taxes payable as per the statute and made applicable from time to time by the concerned authority. DFPCL shall not be responsible for the same.

(G) INDEMNITY

Without prejudice to any other provisions in these conditions, the Contractor shall be bound to keep DFPCL or any representative or employee of DFPCL fully indemnified against any action, claim or proceedings under the provisions of any rules, regulations, bye-laws, notifications, directions or order having the force of law.

The Contractor in contravention of such provisions etc., for the infringement or violation thereof in the course of the execution or completion of the work under the Contract and if, as a result of any such action, claim or proceedings, the Contractor or such representative of the Contractor, as the case may be, adjudged to be liable to any penalties or to pay any penalties or to pay any compensation, such liability, the Contractor and if, DFPCL has to take-over the liability, DFPCL shall deduct all amounts arising out of such liabilities from the Security Deposit of the Contractor or from any other amount due and payable by DFPCL to the Contractor under this Contract or any other Contract and without prejudice to any other legal remedy available to DFPCL.

(H) CONTRACTOR TO COMPLY WITH ALL LAWS ETC. -

The vendor shall be responsible to ensure compliance with all Central and State Laws as well as the Rules, Regulations, Bye-laws and Orders of the Local Authorities and Statutory Bodies as may be in force from time to time. The Tenderer/ Vendor shall give to the statutory bodies, local authorities, police and other relevant authorities all such notices etc. as may be required by law and obtain all requisite Licenses and pay all fees, Duties, Taxes, charges etc. in connection therewith as may be livable on account of his operations involved under this Contract.

The Tenderer/ Vendor shall make good at his own cost any damage to the property of the Company or any other body, persons, local authorities etc due to or arising from operations involved under this Contract and the Company shall have the right to recover the cost of damage from dues payable from the Bank Guarantee or Security Deposit of the Tenderer/ Vendor.

(I) DEDCUTION IF NON-COMPLIANCE OBSERVERED -

If Company's job-controller observes non-compliance by the Contractor in complying with provisions of labour statutes and specific Acts relevant to the Contract, Company shall retain double the value of the non-compliance amount taking into consideration interest, penalty and dues. In case the Company is forced to pay the dues, along with interest and penalty, due to failure of the Contractor, the Company shall be at liberty to recover such amount or any part thereof by deducting it from the Security Deposit or from any sum due by the Company to the Contractor whether under this Contract or otherwise.

(J) CONFIDENTIALITY -

Both during the continuance of this Agreement and 1 (one) year after termination of this Agreement, Vendor and/or his employees/ personnel shall keep all information, such as specifications, technical information, business data and other confidential information under this Agreement strictly confidential and shall not disclose it to any third party or Use it for other purpose than to perform its obligations under this Agreement. Tenderer/ Vendor and/or personnel may disclose the information to an employee of Vendor, or a government agency or other regulating authority

But only insofar as this is necessary either to carry out its duties under this Agreement or comply with any existing law, and under intimation to "Company". Where sub clause (b) applies Vendor and/or personnel shall ensure that the person who receives the information keeps it confidential and does not use it for any unauthorized purpose.

(K) RELATIONSHIP -

Each party understands that they are independent entities and this Agreement does not make it, its/ his employees, associates or agents, the legal representatives of the other party for any purpose whatsoever. Either party has express or implied right or authority to assume or to undertake any obligation in respect of and on behalf of or in the name of the other party or to bind the other party in any manner in respect of any transaction, except the present agreement.

(L) WAIVER -

The failure of either party to enforce at any time any of the provisions of this agreement shall not be considered to be a waiver of the right of such a party thereafter to enforce each and every provision.

(M) ENTIRE AGREEMENT -

This Agreement supersedes all oral and written representations and agreements between the parties, including, but not limited to any earlier agreement relating to the subject matter thereof and/or any other agreement between the parties in relation to the subject matter thereof.

(N) AMENDMENT -

The parties to this Agreement may add, delete, amend or alter all or any of the terms & conditions of this Agreement as mutually agreed from time to time and such modifications and changes shall not be effective until the same are in writing and duly signed by the authorized representatives of both the parties.

(O) DECLARATION OF TENDERERS/ CONTRACTORS RELATION WITH DFPCL EMPLOYEE(S):

Should a Tenderers/ Contractors have a relation or in the case of a firm, one or more of its partners a relation or relations employed in DFPCL or in case of company any of its official or relations employed in DFPCL, the authority inviting tenders shall be informed in writing of the fact at the time of submission of the tender. If so, the name, designation, department and Employee Number of such employees be indicated failing which DFPCL may in its sole discretion reject the tender or rescind the

contract. If any ex-employee(s) of DFPCL is/ are employed, with the Tenderers/ Contractors, name, designation, department and employee number of such employee(s) be indicated and if any ex-employee(s) of DFPCL is/ are employed after acceptance of tender, the said particulars shall also be intimated immediately in writing to DFPCL from time to time. If the Tenderer/ Supplier fails to inform the same, DFPCL shall at sole discretion may reject the tender or rescind the contract.

Scope of Work

Guarantee : 12 Months From The Date Of Completion Of The Job. Any Defect Should Be Rectified By The Contractor On Free Of Cost Basis .

Following Are The Jobs Planned Under The Current Arc Contract

- 1) Miscellaneous Arc Works
- 2) Street Line Pole Foundation Works
- 3) Floor Repairs At Maintenance Work Shops
- 4) Maintenance Of Critical Equipments At Stl Plant
- 5) Maintenance Of Critical Equipments At Stl Plant
- 6) Foundation Repairs At Stl Plant

Terms & Conditions

- 1) Steel will be supplied as free issue
- 2) Water & electricity will be provided by STL free of cost
- 3) All house keeping to be completed by the vendor
- 4) All safety & statutory compliances to be fulfilled by the contractor.
- 5) All unwanted material, debris, broken A.C.Sheets to be taken outside the premises free of cost. No separate payment shall be made for the same.

contractor's scope of supply:- required cement is in contractor's scope

all tools, tackles, equipment etc.required for satisfactory completion
the job.
Required manpower.
To and fro transportation for the above.
Cleaning of site after completion of work
any other items required for completion of the job.

Schedule of penalties for safety violations

Use of PPE is mandatory and non-compliance shall be viewed seriously. Punitive actions including financial penalty may be imposed for safety violations

1 Type of violation-Supervisor found at site without having undergone safety induction training

First Time-Rs.50/- per employee

Repetitions-Rs.100/- Per employee

Frequent Safety violations-Rs.100/- Per employee

2 Type of violation-Employee found without using required safety equipment

First Time-Rs.50/- per employee

Repetitions-Rs.100/- Per employee

Frequent Safety violations-Rs.100/- Per employee + warning letter

3 Type of violation-Employee found without safety belt or without anchoring the safety line at height

First Time-Rs.100/- per employee

Repetitions-Rs.200/- per employee

Frequent Safety violations-Rs.200/- Per employee + warning letter

4 Type of violation-Using defective equipment (Tools&Tackles) at site having potential for accident/fire

First Time-Rs.500/-each Observation

Repetitions-Rs.1000/-each Observation

Frequent Safety violations-Rs.2000/-each Observation + warning letter

5 Type of violation-Non-compliance of HSE&F procedures/standard practises

First Time-Upto

Rs.500/- Repetitions-

Upto Rs.1000/-

Frequent Safety violations-Review for de-listing

6 Type of violation-Carrying out job in an unsafe manner having potential for serious consequences e.g. fall accident, damage to property electrocution etc.

First Time-Rs.1000/-each observation

Repetitions-Rs.2000/-each observation

Frequent Safety violations--Review for de-listing

7 Type of violation-Medical treatment injury

First Time--Upto Rs.500/

Repetitions-Warning letter

Frequent Safety violations--Review for delisting

8 Type of violation-Lost time accident

First Time-Warning letter

Repetitions-Review for de-listing the contractor from approved list

9 Type of violation-Fatal Accident

First Time-Review for de-listing the contractor from approved list.

Type of violation- Misbehavior /Sleeping in the premises

First Time-- Rs.500/ - each observation
Repetitions- Rs 1000/- each observation
Frequent violations--Review for delisting

2. WORKINGHOURS

Normal working time shall be same as the general shift timing of the respective sites. This will be 8 working hours excluding lunch time. However based on the job requirement during the planned /unplanned shutdown/ emergencies or as per plant requirement and instructions of EIC, contractor shall work beyond normal working hours also. No separate / additional compensation shall be payable for the same. (In such cases the contractor has to work as and when required without any percentage increase on SOR.)

3 MOBILIZATION

Contractor shall arrange for necessary materials, workmen and supervision to start the work within 48 hours of instruction from EIC. Incase of emergency or shutdown, contractor shall mobilize all required resources and start the work within 24 hours of instruction of EIC.

Contractor shall initiate gate pass request to EIC, get it counter signed by P&A/IR/Contract Cell and then submit to security in advance as required to mobilize manpower.

4. JOB COMPLETION TIME

For individual works from time to time as and when need arises, separate intimations shall be issued from individual plants/ EIC. Contractor shall ensure mobilization of all required resources and completion of the job including dismantling, etc. as per EIC instructions.

Price Bid Format : Prices to be submitted for regular as well as shutdown jobs.

Line	Service	Short Text	Qty	UOM	Long Text
10	400000	Exc. In all Soils depth upto 2.0 M	1	M3	Excavation for foundation, trenches & for attending underground pipelines, etc in all types of soils, sand,gravel, soft & hard murum, soil mixed with boulders,etc including removing the excavated material upto a distance of 50 Mtrs. beyond the building area and with all lift stacking and spreading as directed, dewatering including pumping, if necessary, shoring and structting, preparing the bed for foundation etc
20	400001	Exc.in all soils depth above 2M upto 3M	1	M3	Excavation for foundation, trenches & for attending underground pipelines, etc in all types of soils, sand,gravel, soft & hard murum, soil mixed with boulders,etc including removing the excavated material upto a distance of 50 Mtrs. beyond the building area and with all lift stacking and spreading as directed, dewatering including pumping, if necessary, shoring and structting, preparing the bed for foundation etc

30	400003	Exc.in hard rock depth 2M to 3M	1	M3	Excavation for foundation, trenches & for attending underground pipelines, etc in in hard rock by using chisel & big pneumatic hammer (measurement with 30% deduction for voids shall be paid & to be stacked properly for measurement) including removing the excavated material upto a distance of 50 Mtrs. Beyond the building area and with all lift stacking and spreading as directed, dewatering including pumping, if necessary, shoring and structting, preparing the bed for foundation etc.
40	400004	Breakof PCC, IPS, WBM/Bitumen layer	1	M3	Breaking of PCC, IPS, MBM/Bitumen layer, removal of rubble soling, breaking brick bat coba etc. at any height using chisel and hammer, removal of debris etc disposal outside the factory premises.
50	400005	Dismantling RCC	1	M3	Dismantling RCC work using pneumatic hammer/chisel, cutting and removal of reinforcement etc. to be collected and kept separately for handing over to stores and disposal of debris of concrete outside the plant premises.
60	400006	Dressing area upto depth 150 mm	1	M2	Dressing over area upto average depth of 150mm and removing excess material out side the plant premises as directed.
70	400007	Rem excavated spoil/debris outside	1	M3	Removing excavated spoil/dismantled debris to outside the premises.
80	400008	Rem excavated spoil/debris inside	1	M3	Removing excavated spoil/dismantled within the land premises at low area to be dressed and leveled as directed by the Engineer Incharge

90	400009	Filling available earth in plinth	1	M3	Filling available Earth in plinth and floors with approved excavated materials in 15cm to 20cm layers including watering and compacting completing as specified and directed.
100	400011	Prov. & laying 230mm rubble soling	1	M2	Providing and laying 230 mm thick dry rubble packing under floor including laying in regular lines and level filling in the interstices with long chips, spalls and sand well rammed, watered and consolidated etc. as specified and directed.
110	400012	Prov.& lay 150mm thk dry rubble soling	1	M2	Providing and laying 150 mm thick dry rubble soling under floor including laying in regular lines and level filling in the interstices with long chips, spalls and sand well rammed, watered and consolidated etc. as specified and directed.
120	400015	Prov. & laying 115mm thk brick soling	1	M2	Providing and laying on the consolidated subgrade 115 mm thick brick soling in regular lines, level, filling in the joints sand, watering etc. complete as specified and directed.
130	400016	Prov. 230mm dry rubble stone pitching	1	M2	Providing 230mm thick dry rubble stone pitching laid on sides and bottom wherever required including one header 30 cm long @ 1 per 2.5m ² including pointing the joints with cement mortar 1:4, curing etc complete as specified and directed.
140	400017	Prov. & filling sand in 15cm to 20cm	1	M3	Providing and filling sand in 15cm to 20 cm layers well compacted and watered as directed.

150	400019	Prov. mixng & lay plain concrete M-100	1	M3	Providing, mixing & laying plain concrete of any thickness below footing, plinth beams, drains, flooring, paving, pedestals, etc. using graded stone aggregate including form work consolidation, finishing etc. complete and curing. (Rate applicable for depth below GL, not exceeding 3 mtr and height not exceeding 1st floor)
160	400020	Prov. mixng & lay. plain concrete M-150	1	M3	Providing, mixing & laying plain concrete of any thickness below footing, plinth beams, drains, flooring, paving, pedestals, etc. using graded stone aggregate including form work consolidation, finishing etc. complete and curing. (Rate applicable for depth below GL, not exceeding 3 mtr and height not exceeding 1st floor)
170	400572	Supply of tractor	1	DAY	<p>Contractor's Scope :</p> <p>1. HIRING OFJ TRACTOR VEDOR TO PROVIDE TRACTOR WITH A QUALIFIED OPERATOR WITH ALL STATUTORY DOCUMENTS</p> <p>2.VEDOR ALSO ALONG WITH PUC DRIVER LICENSE / CERTIFICATE.</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>

180	400022	P&L RCC M-150 for foundation,beam,col	1	M3	Providing, mixing, laying cast in situ RCC concrete, mechanically mixed, vibrated and finished in line and level curing etc. with mix 20mm size graded aggregate in foundation, equipment foundation, plinth beams, beams, columns, RCC walls, vertical / circular lintel beams, beams excluding sunshades, roof slabs, staircase, waist slamb / steps, louves etc. Rate applicable for depth below GL not exceeding 3m & height not exceeding 1st floor including shuttering/ centering complete reinforcement steel shall be paid seperately.
190	400023	P&L RCC M-200 for foundation,beam,col	1	M3	Providing, mixing, laying cast in situ RCC concrete, mechanically mixed, vibrated and finished in line and level curing etc. with mix 20mm size graded aggregate in foundation, equipment foundation, plinth beams, beams, columns, RCC walls, vertical / circular lintel beams, beams excluding sunshades, roof slabs, staircase, waist slamb / steps, louves etc. Rate applicable for depth below GL not exceeding 3m & height not exceeding 1st floor including shuttering/ centering complete reinforcement steel shall be paid seperately.

200	400024	P&L RCC M-250 for foundation,beam,col	1	M3	Providing, mixing, laying cast in situ RCC concrete, mechanically mixed, vibrated and finished in line and level curing etc. with mix 20mm size graded aggregate in foundation, equipment foundation, plinth beams, beams, columns, RCC walls, vertical / circular lintel beams, beams excluding sunshades, roof slabs, staircase, waist slamb / steps, louves etc. Rate applicable for depth below GL not exceeding 3m & height not exceeding 1st floor including shuttering/ centering complete reinforcement steel shall be paid seperately.
210	400025	P&L RCC in foundation etc for addl floor	1	M3	Providing, mixing, laying cast in situ RCC concrete, mechanically mixed, vibrated and finished in line and level curing etc. with mix 20mm size graded aggregate in foundation, equipment foundation, plinth beams, beams, columns, RCC walls, vertical / circular lintel beams, beams excluding sunshades, roof slabs, staircase, waist slamb / steps, louves etc. Rate applicable for depth below GL not exceeding 3m & height not exceeding 1st floor including shuttering/ centering complete reinforcement steel shall be paid seperately. (1st floor for every additional floor.)
220	400026	P&L RCC M-150 for roof slab,canopy etc	1	M3	Providing, mixing, laying RCC concrete mechanically mixed, vibrated and finished in line and level, curing etc. for RCC roof slabs, canopy, sunshades, louvers, fins, staircases, for all thickness upto first floor including shuttering.

230	400027	P&L RCC M-200 for roof slab,canopy etc	1	M3	Providing, mixing, laying RCC concrete mechanically mixed, vibrated and finished in line and level, curing etc. for RCC roof slabs, canopy, sunshades, louvers, fins, staircases, for all thickness upto first floor including shuttering.
240	400028	P&L RCC in roofslab etc for addl floors	1	M3	Providing, mixing, laying RCC concrete mechanically mixed, vibrated and finished in line and level, curing etc. for RCC roof slabs, canopy, sunshades, louvers, fins, staircases, for all thickness upto first floor including shuttering. (for additional floors)
250	400029	Providing precast slabs (RCC) M - 150	1	M3	Providing precast slabs (RCC) M - 150 as per detailed drawing & the design including shuttering,mechanically mixed concrete,curing etc. including hoisting, fixing, complete of any thickness 50mm to 200mm (reinforcement shall be paid separately).
260	400030	Prov. M-150 RCC concrete for RCC road	1	M3	Providing M-150 RCC concrete for RCC rod, paving as per drawing and details in panels including form work, curing etc. complete. Concrete shall be mechanically mixed and vibrated and finished in line & level as per specification and directed by Engineer-Incharge. Reinforcement shall be paid seperately.
270	400032	Leaving pocket upto depth 300mm	1	EA	Leaving pocket not exceeding 0.1 m2 in concrete structures inclusive of fixing, shuttering and removal, in proper location, size and level while concrete and grouting the same after fixing the bolts etc. complete as specified and directed.

280	400033	Leaving pocket depth 300-800mm	1	EA	Leaving pocket not exceeding 0.1 m2 in concrete structures inclusive of fixing, shuttering and removal, in proper location, size and level while concrete and grouting the same after fixing the bolts etc. complete as specified and directed.
290	400034	25mm grouting with OP cement	1	M2	25mm grouting below base plates and frames with cement mortar 1:3 including necessary form work compacting, curing etc. complete as specified and directed.
300	400036	25mm grouting using GP2 or equivalent	1	M2	25mm grouting below base plates and frames with cement mortar 1:3 including necessary form work compacting, curing etc. complete as specified and directed.
310	400037	Prov & mixng water proofing compound	1	KG	Providing and mixing Cico/Inperno/other approved quality water proofing compound in concrete and in plaster at 3 1/4 by weight of cement or as per manufacturers instruction for work wherever specified.
320	400041	Pressure grouting	1	M2	Pressure grouting : Water proofing of RCC structures like roof slabs, water tanks underground structures etc. by pressure grouting with non-shrink water proof grouting compound as per specification including fixing of nozzles, supply of all materials, labour complete in all respect and as per direction of the engineer.

330	400043	Fab. & Fix. reinforce deformed bars	1	MT	<p>Fabrication and fixing of reinforcing bars of any dia from 6mm to 32mm including cutting, bending and placing in position and tying with binding wires of 18 SQG as per detail design and drawing specifications for various diameters of bar for all RCC works at any level including de-rusting and strengthening bars supply. The cover to the reinforcement must cover the reinforcement, must be strictly adhered to by means of cement blocks, spacers, or chairs etc. will be measured for payment. Steel shall be issued from DFPCL Stores. Necessary carting etc. by the contractor. Contractor to submit reconciliation of issue material & balance steel to be returned to stores.</p>
340	400044	Brick masonry in cement mortar (1:5)	1	M3	<p>Providing first class burnt brick masonry in foundation & upto first f level in storm water drains, trenches etc. and plinth including dewatering, racking out joints on exposed faces and watering etc. & inclusive of scaffolding complete as specified & directed in cement</p>
350	400572	Supply of tractor	1	DAY	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1. HIRING OF J TRACTOR VEDOR TO PROVIDE TRACTOR WITH A QUALIFIED OPERATOR WITH ALL STATUTORY DOCUMENTS 2. VEDOR ALSO ALONG WITH PUC DRIVER LICENSE / CERTIFICATE. <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.

360	400046	Prov. 115mm thk 1st class burnt bricks	1	M2	Providing 115 mm thick first class burnt bricks or cement masonry with conventional IS standard bricks in cement mortar 1:4 including scaffolding, racking out joints and watering etc. complete as specified & directed including providing of RCC runner as specified in technical specifications upto first floor.
370	400047	Prov.115mm 1st class burnt brick adl.Fl.	1	M2	Providing 115 mm thick first class burnt bricks or cement masonry with conventional IS standard bricks in cement mortar 1:4 including scaffolding, racking out joints and watering etc. complete as specified & directed including providing of RCC runner as specified in technical specifications upto first floor.
380	400048	Providing random rubble masonry	1	M3	Providing random rubble (best locally available stone) in cement mortar 1:5 in foundation, compound wall, culvert, barriers and plinth including de-watering and racking out joints on exposed faces and providing headers @ one in every 2.5 m2 of masonry with corner stones as required with masonry brought to courses at every 1.5 mtr height, curing etc. complete as directed.
390	400049	Making holes in 230mm brick wall	1	EA	Making holes of reqd size in 230mm brick wall for exhaust fan and making good the same in CM 1:4.
400	400050	Providing cement plaster in 15mm thk	1	M2	Providing cement plaster in a single coat in cement mortar 1:4 with neeru finish to concrete bricks or stone masonry surfaces in all position and in all lifts including scaffolding and curing as specified and directed at any level.

410	400051	12mm thk ordinary cement plaster 1 coat	1	M2	Providing cement plaster in a single coat in cement mortar 1:4 with neeru finish to concrete bricks or stone masonry surfaces in all position and in all lifts including scaffolding and curing as specified and directed at any level.
420	400052	Cement plaster in 15mm thk addl. Fr.	1	M2	Providing cement plaster in a single coat in cement mortar 1:4 with neeru finish to concrete bricks or stone masonry surfaces in all position and in all lifts including scaffolding and curing as specified and directed at any level. (for every additional floor)
430	400053	Cement plaster in 12mm thk addl. Fr.	1	M2	Providing cement plaster in a single coat in cement mortar 1:4 with neeru finish to concrete bricks or stone masonry surfaces in all position and in all lifts including scaffolding and curing as specified and directed at any level. (for every additional floor)
440	400055	Prov. sand faced plaster in 20mm thk	1	M2	Providing sand faced plaster in 2 coats (cement mortar for base coat 1:4 and finish coat 1:3) including scaffolding, keeping the surface of the base coat rough to receive the sand faced treatment, finishing the surface by exposing to sand grains by sponging and curing it including grooves, drip moulding etc. complete as specified and directed.

450	400056	Prov. sand faced plaster for addl. Fl.	1	M2	Providing sand faced plaster in 2 coats (cement mortar for base coat 1:4 and finish coat 1:3) including scaffolding, keeping the surface of the base coat rough to receive the sand faced treatment, finishing the surface by exposing to sand grains by sponging and curing it including grooves, drip moulding etc. complete as specified and directed. (For additional Floor)
460	400057	Cement pointing flush on brick masonry	1	M2	Cement pointing flush, raised or sunk in CM 1:3 watering, scaffolding all complete as per specification and instruction of
470	400058	Cement pointing flush on rubble masonry	1	M2	our Consultant/Engineer. Cement pointing flush, raised or sunk in CM 1:3 watering, scaffolding all complete as per specification and instruction of our Consultant/Engineer
480	400059	Removal of damage plastering of any thk.	1	M2	Removal of damage plastering of any thickness in proper shape upto surface of the brick work / concrete and cleaning thoroughly the existing brick / concrete surface with wire brush etc. including scaffolding, removal of debris and disposal outside the plant premises.
490	400060	Prov. & laying Indian Patent Stone 40mm	1	M2	Providing and laying Indian Patent Stone in 1:2:3 cement concrete using 12 mm and below grit and sand mixed aggregate to the average thickness specified and laid in alternate panels of 6 Sq.M. The top to be trowelled smooth and cured for a period of atleast 7 days and completed as per specifications at all levels and directions of our Engineer.

500	400064	Fixing insert plates, bolts, pipes	1	KG	Fixing insert plates, bolts, pipes etc. in position as required and grouting the same in the concrete as directed.
510	400068	Prov.& fix. spartek or eq.Ceramic tiles	1	M2	Providing and fixing spartek or equivalent ceramic floor and dado tiles, bedding materials in CM 1:4 as per specifications including filling the joints with joint filler of matching colour (contractor shall also quote basic price of tiles and make).
520	400070	P & L 30mm thk kota stone for flooring.	1	M2	Providing and laying polished 30mm thk kota stone for flooring on 1:2 line mortar including cement float, filling the joints with cement slurry, curing polishing, rubbing, cleaning etc. complete.
530	400071	P & L 30mm thk kota stone for skirting.	1	RM	Providing and laying polished 30mm thk kota stone for 150mm high skirting on 1:4 cement mortar backing with cement float, filling joints with cement slurry, curing, polishing, rubbing and cleaning etc. complete.
540	400072	Polishing existing kota stone fl.	1	M2	Polishing, rubbing and cleaning the existing kota stone flooring with necessary grinding machine, tools etc complete.
550	400073	Polishing, rubbing and cleaning skirtin	1	RM	Polishing, rubbing and cleaning the existing 150mm high skirting with necessary tools etc. complete.
560	400074	Providng and fixing polished kadappa	1	M2	Providing and fixing both sides polished black kadappa 25, 240mm thk in line and level in cement mortar as per design and specification and as directed.
570	400075	Providing and spreading gravel.	1	M2	Providing and spreading gravel / metal over areas including dressing in line and level 75-100mm thick as directed.

580	400076	Providing Kaddapa partition for urinal	1	M2	Providing partition for urinal of 30mm thick machine cut and machine polished on both sides and edges kadappa stone of approved shape, quality including cutting holes of reqd. sizes in the appropriate places to receive pipes etc. fixing in cement mortar 1:3 curing and cleaning complete.
590	400077	Providing Marble partition for urinal	1	M2	Providing partition for urinal of 20mm thick machine cut & machine polished on both sides and edges marble slab of approved shape, quality including cutting holes of reqd. sizes in the appropriate places to receive pipes etc. fixing in cement mortar 1:3 curing and cleaning complete.

600	400078	Providing water proofing to terrace slab	1	M2	Providing water proofing to terrace slab with average 100mm thick concrete of broken bricks bats and cement mortar 1:5 in the proportion of 2 parts of brick bat and 1 part of mortar, laid to prepare slope of mortar, well rammed, watered and consolidated with vatta 15 cm at junctions of walls and IPS flooring 1:2:3 (12.5 mm chips) 40mm thk with an admixture of approved water proofing compound CICO / Inperno or of any approved quality as per manufacturer's specification laid after grouting the surface of brick bat coba with neat cement slurry in alternate suitable squares to reqd slope as direct including filling in joints with bitumen & clearing the slab top of all dust and loose material tamping, finishing and curing complete as directed and specified (horizontal measurement clear between walls and will be paid for)
610	400146	Supply & fixing anchor fasteners 12mm d	1	EA	Anchor Fasteners : supplying and fixing anchor fasteners to the RCC columns, beams, slabs a masonry walls at any elevation including necessary scaffolding and drilling tools etc.
620	400147	Supply & fixing anchor fasteners 16mm d	1	EA	Anchor Fasteners : supplying and fixing anchor fasteners to the RCC columns, beams, slabs a masonry walls at any elevation including necessary scaffolding and drilling tools etc.
630	400148	Supply & fixing anchor fasteners 20mm d	1	EA	Anchor Fasteners : supplying and fixing anchor fasteners to the RCC columns, beams, slabs a masonry walls at any elevation including necessary scaffolding and drilling tools etc.

640	400149	Supply & fixing anchor fasteners 25mm d	1	EA	Anchor Fasteners : supplying and fixing anchor fasteners to the RCC columns, beams, slabs a masonry walls at any elevation including necessary scaffolding and drilling tools etc.
650	400171	Rolling with 10-12 tons road rollers	1	M2	Rolling formation level with 10-12 tons road rollers
660	400172	Supply & filling murrum in layers	1	M3	Supplying and filling approved quality murrum in layers 250-300mm thick, watering, rolling with 10-12 ton road roller, consolidating complete as directed.
670	400175	P&F position with road kerbstone	1	RM	Providing & fixing position in line and level alongwith road Kerb stones of 1:3:6 concrete mix with 6mm dia nominal reinforcement as per design drawing including curing complete as directed.
680	400178	P&L R.C hume pipe NP2-150mm d	1	RM	Providing and laying R.C hume pipe HP 2 class with collar, jointing, filling with cement mortar 1:1 complete as directed.
690	400179	P&L R.C hume pipe NP2-250mm d	1	RM	Providing and laying R.C hume pipe HP 2 class with collar, jointing, filling with cement mortar 1:1 complete as directed.
700	400180	P&L R.C hume pipe NP2-350mm d	1	RM	Providing and laying R.C hume pipe HP 2 class with collar, jointing, filling with cement mortar 1:1 complete as directed.
710	400181	P&L R.C hume pipe NP2-450mm d	1	RM	Providing and laying R.C hume pipe HP 2 class with collar, jointing, filling with cement mortar 1:1 complete as directed.
720	400182	P&L R.C hume pipe NP2-600mm d	1	RM	Providing and laying R.C hume pipe HP 2 class with collar, jointing, filling with cement mortar 1:1 complete as directed.
730	400194	Bricks (per 1000 Nos.)	1	EA	Supply fo bricks (per 1000 nos.)
740	400196	Aggregate no.1 & 2 (per Brass)	1	EA	Supply of Agreegate no. 1 & 2 (per Brass)
750	400199	Aggregate no.3 (per Brass)	1	EA	Supply of Aggregate no.3 (per Brass)

760	400201	Murrum (per Brass)	1	EA	Supply of Murrum (per Brass)
770	400202	Quarry dust (brass)	1	EA	Supply of Quarry dust (per Brass)
780	400203	Mason	1	DAY	Supply of Mason
790	400204	Carpenter (furniture)	1	DAY	Supply of Carpenter (furniture)
800	400205	Carpenter (shuttering)	1	DAY	Supply of Carpenter (shuttering)
810	400209	Male labourer	1	DAY	Supply of Carpenter (shuttering)
820	400351	Pro.const.sanitary900mmx600mm brck msnry	1	EA	<p>Providing and constructing brick masonry inspection chamber with 900mm x600mm internal dimensions depth not exceeding 1:2m including excavation, re-filling and the following: 1:3:6 PCC, 150 thick and 75mm offset in foundation. 230mm thick masonry in cement mortar 1:6 M15 PCC benching and channeling including formation of channels slopes and finishing with 20 mm thk cment plaster in 1:4 cement mortar finished smooth with rendering coat of neat cement water proofing compound on inside 75mm thick 1000mm x 700mm RCC precast cover slab (M20) including reinforcement 2 nos. lifting holes/hols all joints well sealed etc. complete as per specifications, drawings and as directed by owner/consultant.</p>

830	400352	Const.brick msnry manhole dpth upto 2.0m	1	EA	Construction brick masonry manholes 1200mm x 900mm internal dimention including excavation, 150mm thick 1:3:6 PCC in formation with 150mm offsets, 230mm thick brick masonry upto 1.2m depth from top & brick masonry 350mm thick for masnory below 1.2 m depth below with cement plaster finished smooth with neat cement 1:2:4 PCC in benching and channeling of surface finished smooth and channel formed to size and levels, including providing and fixing M.S. rung patterns one as per reinforcement 2 nos. Lifting holes/hoks all joints well selaed and curb angle at manhole cover opening to IS 5455 & covered with precast cover slab of 75mm thick x 1000x1300 mm long having 2 lifting hooks. for depth upto 2.0m.
840	400353	Pro.fix precast M20 Gr.conc.cvr 75mm thk	1	M2	Providing and fixing precast M20 grade concrete cover including concreting curing reinforcement with necessary provision for lifting formwork, transporting etc. complete as per specificaiton drawings and as directed by owner/consultant (reinforcement to be paid separately).

850	400384	Sply fab,fix M.S.bolts 10mm to 24mm dia	1	KG	<p>Supply, fabrication, casting, installing and fixing in position M.S. holding down threaded bolts nuts washers, anchor plates pipes sleeves etc. for equipment tanks, vessels, structural steel columns etc. including supplying, fabricating and installing necessary templates, providing auxillary dummy structures, if any, necessary tying and welding to reinforcement adjustment of shuttering greasing exposed metal surfaces and covering with juts cloth etc. complete and as per drawings and specifications and as directed by the owner/consultant. Note:- fo templetes and auxilary dummy supports reinforcement rods/structural steel will be supplied free of cost of contractor & will be paid for under steel structurals. Bolts from 10mm and upto 24mm dia.</p>
860	400395	Pr. & fix CI rain water pipes 100mm dia	1	RM	<p>Providing , fixing CI rain water pipes of NECO brand in position and Jointing with spun yarn and CM 1:4 rain water pipes including bends shoes, MS clamps fixed to masonry or concrete surfaces etc. complete.</p>
870	400469	Prov. & shuttering below G.L.	1	M2	<p>Contractor's Scope : 1) PROVIDING AND FIXING OF SHUTTERING OF M.S. PLATE / PLYWOOD COMPLETE 2)THE SCAFFOLDING, SUPPORT, WALKWAY, ETC REQUIRED ARE IN THE SCOPE OF CONTRACTOR. 3) APPLICATION OF SHUTTERING OIL . 4) NECESSARY PERMITS TO BE TAKEN & SAFETY RULES , REGULATIONS MUST BE FOLLOWED. DFPCL Scope : 1) Electricity, water will be provided free of Cost for work inside DFPCL premises. 2) The board to be fixed will be provided by DFPCL.</p>

880	400470	Prov. & shuttering above G.L.	1	M2	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1) PROVIDING AND FIXING OF SHUTTERING OF M.S. PLATE / PLYWOOD COMPLETE 2)THE SCAFFOLDING, SUPPORT, WALKWAY, ETC REQUIRED ARE IN THE SCOPE OF CONTRACTOR. 3) APPLICATION OF SHUTTERING OIL . 4) NECESSARY PERMITS TO BE TAKEN & SAFETY RULES , REGULATIONS MUST BE FOLLOWED. <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water will be provided free of Cost for work inside DFPCL premises. 2) The board to be fixed will be provided by DFPCL.
890	400476	P/L RCC M20 READY MIX CONCRETE	1	M3	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1) Providing and laying M-20 grade RCC of trap metal in position inclusive of all material 2) Finishing and compacting by vibrator. 3) Curing of concrete by hessian cloth / ponding. 4) 20mm size graded aggregate in foundation, equipment foundation, plinth beams, beams, columns, RCC walls, vertical / circular lintel, beams, beams excluding sunshades, roof slabs, staircase, waist slamb / steps, louves etc. 5) Rate applicable for depth below GL not exceeding 3m <(>&<)> height not exceeding 1st floor including shuttering/ 6) Centering complete reinforcement steel shall be paid seperately. <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.

900	400477	P/L RCC M25 READY MIX CONCRETE	1	M3	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1) Providing and laying M-25 grade RCC of trap metal in position inclusive of all material 2) Finishing and compacting by vibrator. 3) Curing of concrete by hessian cloth / ponding. 4) 20mm size graded aggregate in foundation, equipment foundation, plinth beams, beams, columns, RCC walls, vertical / circular lintel, beams, beams excluding sunshades, roof slabs, staircase, waist slamb / steps, louves etc. 5) Rate applicable for depth below GL not exceeding 3m <(>&<)> height not exceeding 1st floor including shuttering/ 6) Centering complete reinforcement steel shall be paid seperately. <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.
910	400484	P/f granait for partetion,sill,platform	1	M2	<p>Contractor's Scope :</p> <p>PROV&FIXING GRANAIT 18 MM WITH ALL MOULDING.</p> <ol style="list-style-type: none"> 1. Prov.& laying pre polished granite in cm 1:3 for floor,sill,partion,platform ,includes all moulding,joint filling,grouting,polishing maintaining line level,of pre approved quality colour,material "with all labour & materials etc. <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water will be provided free of Cost for work inside DFPCL premises. 2) CEMENT FREE OF COST.

920	400485	P/F VETRIFIED FLOOR AND WALL TILE	1	M2	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1. Prov/fixing approved quality ,pattern,coloued verified floor,wall tiles in cm 1:3 including cutting,filling joints with cement or filler material,keping spacer with maintaining line,,levell,pattern etc. 2. Including all material,tools,tackles. 3.Tile make-Kajarial / Johnson. <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1. Electricity, water will be provided free of Cost for work inside DFPCL premises. 2. CEMENT FREE OF COST.
930	400486	P/L PCC M10 READY MIX CONCRETE	1	M3	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1. Providing, mixing & laying plain concrete of any thickness below footing, plinth beams, drains, flooring, paving, pedestals, etc. 2. Using graded stone aggregate including form work consolidation,finishing etc. complete and curing. (Rate applicable for depth below GL, not exceeding 3 mtr and height not exceeding 1st floor) 3. Centering complete reinforcement steel shall be paid seperately. <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.

940	400509	P/S of dewatering 5 HP diesel pump	1	DAY	<p>VENDOR SCOPE-</p> <p>1)PROVIDING 5 HP TO 10 HP DIESEL OPERATED PUMPS ON 24 HOURS " AS WHEN REQUIRED" OPERATION BASIS.</p> <p>2)ALL CONSULMABLES FUEL OIL AND NECESSARY MAINTENANCE INCLUDING OPERATION AS PER THE INSTRUCTIONS OF OUR JOB CO-ORDINATOR WITH SUCTION HOSE OF 5 METERS LONG AND DELIVERY HOSE OF 15 METERS LONG</p> <p>3) ALL TOOLS, TACKLES, EQUIPMENTS, CONSUMABLES ETC.</p> <p>4COMPETENT MANPOWER.</p> <p>DFPCL Scope :</p> <p>1) Electricity, water will be provided free of Cost for work inside DFPCL</p> <p>2) Issuing the permit after complete preparation by Contractor.</p>
950	400510	Prov. & supply pump operator	1	DAY	<p>Contractor's Scope :</p> <p>1) SUPPLIED OF SKIILED PUMP OPERATOR FOR DEWATERING</p> <p>2) REQUIRED TOOLS AND TRACKLES IN CONTRACTOR SCOPE</p> <p>DFPCL Scope :</p> <p>1) Electricity, water will be provided free of Cost for work inside DFPCL</p> <p>2) Issuing the permit after complete preparation by Contractor.</p>

960	400511	Dewatering using 3 HP ELE. Pumps	1	DAY	<p>Contractor's Scope :</p> <p>1)PROVIDING 5 HP ELE. OPERATED PUMPS ON 24 HOURS " AS & WHEN REQUIRED" OPERATION BASIS.</p> <p>2)ALL CONSULMABLES NECESSARY MAINTENANCE INCLUDING OPERATION AS PER THE INSTRUCTIONS OF OUR JOB CO-ORDINATOR WITH SUCTION HOSE OF 5 METERS LONG AND DELIVERY HOSE OF 15 METERS LONG</p> <p>3) ALL TOOLS, TACKLES, EQUIPMENTS, CONSUMABLES ETC.</p> <p>4)COMPETENT MANPOWER.</p> <p>DFPCL Scope :</p> <p>1) Electricity, water will be provided free of Cost for work inside DFPCL premises.</p> <p>2) Issuing the permit after complete preparation by Contractor.</p>
970	400543	Providing core cutting 100 mm dia.	1	EA	<p>Contractor's Scope :</p> <p>1) PROVIDING AND DIMOND CORE CUTTING 100MM DIA X 200 MM DEPTH</p> <p>2) DEPLOYED SKILL LABOUR FOR THIS JOB</p> <p>3) REQUIRED TOOLS AND TRACKLES IN CONTRACTOR SCOPE</p> <p>DFPCL Scope :</p> <p>1) Electricity, water will be provided free of Cost for work inside DFPCL</p> <p>2) Issuing the permit after complete preparation by Contractor.</p>

980	400544	Providing core cutting 150 mm dia.	1	EA	<p>Contractor's Scope :</p> <p>1) PROVIDING AND DIMOND CORE CUTTING 150MM DIA X 200 MM DEPTH</p> <p>1) SUPPLIED OF SKIILED PUMP OPRATOR FOR DEWATERING</p> <p>2) REQUIRED TOOLS AND TRACKLES IN CONTRACTOR SCOPE</p> <p>DFPCL Scope :</p> <p>1) Electricity, water will be provided free of Cost for work inside DFPCL</p> <p>2) Issuing the permit after complete preparation by Contractor.</p>
990	400545	Providing core cutting 200 mm dia.	1	EA	<p>Contractor's Scope :</p> <p>1) PROVIDING AND DIMOND CORE CUTTING 200 MM DIA X 400 MM DEPTH</p> <p>1) SUPPLIED OF SKIILED PUMP OPRATOR FOR DEWATERING</p> <p>2) REQUIRED TOOLS AND TRACKLES IN CONTRACTOR SCOPE</p> <p>DFPCL Scope :</p> <p>1) Electricity, water will be provided free of Cost for work inside DFPCL</p> <p>2) Issuing the permit after complete preparation by Contractor.</p>

1000	400559	Prov. & Lay.RMC (Batching plant), M30	1	M3	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1) Providing and laying M-30 grade RCC of trap metal in position inclusive of all material 2) Finishing and compacting by vibrator. 3) Curing of concrete by hessian cloth / ponding. 4) 20mm size graded aggregate in foundation, equipment foundation, plinth beams, beams, columns, RCC walls, vertical / circular lintel, beams, beams excluding sunshades, roof slabs, staircase, waist slamb / steps, louves etc. 5) Rate applicable for depth below GL not exceeding 3m <(><<)>(><&<)> <(><<)> height not exceeding 1st floor including shuttering/ 6) Centering complete reinforcement steel shall be paid seperately. <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.
1010	400560	Extra over concret.for addl.floor,5-10m	1	M3	<p>Contractor's Scope :</p> <p>Providing, mixing & laying plain concrete of any thickness below footing, plinth beams, drains, flooring, paving, pedestals, etc. using graded stone aggregate including form work consolidation, finishing etc. complete and curing. (Rate applicable for additional floor vertical level 5 m to 10 m level)</p> <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.

1020	400561	Extra over concret.for addl.floor,10-15m	1	M3	<p>Contractor's Scope :</p> <p>Providing, mixing & laying plain concrete of any thickness below footing, plinth beams, drains, flooring, paving, pedestals, etc. using graded stone aggregate including form work consolidation, finishing etc. complete and curing. (Rate applicable for additional floor vertical level 10 m to 15 m level)</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>
1030	400562	Extra over concret.for addl.floor,20-25m	1	M3	<p>Contractor's Scope :</p> <p>Providing, mixing & laying plain concrete of any thickness below footing, plinth beams, drains, flooring, paving, pedestals, etc. using graded stone aggregate including form work consolidation, finishing etc. complete and curing. (Rate applicable for additional floor vertical level 20 m to 25 m level)</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>

1040	400563	Extra over bk msnry.for addl.floor5-10m	1	M3	<p>Contractor's Scope :</p> <p>Providing first class burnt brick masonry in foundation & upto first f level in storm water drains, trenches etc. and plinth including dewatering, racking out joints on exposed faces and watering etc. & inclusive of scaffolding complete as specified & directed in cement Rates applicable for additional floor vertical level 5 m to 10 M level</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>
1050	400564	Extra over bk msnry.for addl.floor10-15m	1	M3	<p>Contractor's Scope :</p> <p>Providing first class burnt brick masonry in foundation & upto first f level in storm water drains, trenches etc. and plinth including dewatering, racking out joints on exposed faces and watering etc. & inclusive of scaffolding complete as specified & directed in cement Rates applicable for additional floor vertical level 10 m to 15 M level</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>

1060	400565	Extra over bk msnry.for addl.floor15-20m	1	M3	<p>Contractor's Scope :</p> <p>Providing first class burnt brick masonry in foundation & upto first f level in storm water drains, trenches etc. and plinth including dewatering, racking out joints on exposed faces and watering etc. & inclusive of scaffolding complete as specified & directed in cement Rates applicable for additional floor vertical level 15 m to 20 M level</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>
1070	400566	Extra over bk msnry.for addl.floor20-25m	1	M3	<p>Contractor's Scope :</p> <p>Providing first class burnt brick masonry in foundation & upto first f level in storm water drains, trenches etc. and plinth including dewatering, racking out joints on exposed faces and watering etc. & inclusive of scaffolding complete as specified & directed in cement Rates applicable for additional floor vertical level 15 m to 20 M level</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>

1080	400567	Extra over plaster for addl.floor5-10m	1	M3	<p>Contractor's Scope :</p> <p>Providing sand faced plaster in 2 coats (cement mortar for base coat 1:4 and finish coat 1:3) including scaffolding, keeping the surface of the base coat rough to receive the sand faced treatment, finishing the surface by exposing to sand grains by sponging and curing it including grooves, drip moulding etc. complete as specified and directed.</p> <p>Rates applicable for additional floor vertical level 5 m to 10 M level</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>
1090	400568	Extra over plaster for addl.floor10-15m	1	M3	<p>Contractor's Scope :</p> <p>Providing sand faced plaster in 2 coats (cement mortar for base coat 1:4 and finish coat 1:3) including scaffolding, keeping the surface of the base coat rough to receive the sand faced treatment, finishing the surface by exposing to sand grains by sponging and curing it including grooves, drip moulding etc. complete as specified and directed.</p> <p>Rates applicable for additional floor vertical level 5 m to 10 M level</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>

1100	400569	Extra over plaster for addl.floor15-20m	1	M3	<p>Contractor's Scope :</p> <p>Providing sand faced plaster in 2 coats (cement mortar for base coat 1:4 and finish coat 1:3) including scaffolding, keeping the surface of the base coat rough to receive the sand faced treatment, finishing the surface by exposing to sand grains by sponging and curing it including grooves, drip moulding etc. complete as specified and directed.</p> <p>Rates applicable for additional floor vertical level 5 m to 10 M level</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>
1110	400570	Supply of sewage cleaner (bhangi)	1	DAY	<p>Contractor's Scope :</p> <p>1) Supply of sewage cleaner for chamber cleaning</p> <p>2) All safety PPE 'S supply by contractor</p> <p>DFPCL Scope :</p> <p>1) Electricity, water, Safety permit will be provided free of Cost for work inside DFPCL premises.</p>

1120	400602	Prov. & Laying Non Shrink grout GP2 or e	1	M3	<p>Contractor's Scope :</p> <p>1) Providing & Laying Non Shrinking Conbextra Grout GP2 of fosroc make under base Plate of foundation/pockets, etc.</p> <p>2) The grout to be laid as per specifications in drawing & also manufacturer's specifications to be followed.</p> <p>DFPCL Scope :</p> <p>1) Electric supply & Water will be provided free of cost for works within company premises.</p> <p>SAFETY PRECAUTIONS</p> <p>The contractor shall follow safety rules & regulations, safety procedures as per the safety standards and comply with the safety requirements.</p> <p>The contractor is required to deploy persons for specific jobs who are trained and skilled in particular trade and well familiar with hazards and safety precautions.</p> <p>The site staff and workers of the contractors are required to undergo safety orientation before they are assigned work at site. No person shall be allowed at work site without safety orientation.</p> <p>The contractor shall ensure that any time during the performance of the work his personnel are fit to execute the tasks assigned and are not under the influence of any alcoholic liquor, drug or other intoxicating substances.</p> <p>"The contractor shall provide personal protective equipment as specified to it's staff and workmen such as, safety helmets, safety shoes, safety goggles, ear plugs, hand gloves, safety harness / belts, overalls, gum boots etc. and other work equipment as required for safe execution of work at his cost. Special PPEs/ safety appliances, if required for any job as mentioned below job may be provided by the company on chargeable / returnable basis (cost of repair or damage as a result of mishandling will be charged from the contractor)."</p>
------	--------	------------------------------------------	---	----	---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------

WORKINGHOURS

"Normal working time shall be same as the general shift timing of the respective sites. This will be 8 working hours excluding lunch time. However based on the job requirement during the planned /unplanned shutdown/ emergencies or as per plant requirement and instructions of EIC, contractor shall work beyond normal working hours also. No separate / additional compensation shall be payable for the same."

MOBILIZATION

Contractor shall arrange for necessary materials, workmen and supervision to start the work within 48 hours of instruction from EIC. In case of emergency or shutdown, contractor shall mobilize all required resources and start the work within 24 hours of instruction of EIC. To & fro transportation of the equipment shall be arranged by contractor. However mobile crane/tractor, EOT/ HOT facilities, if required for loading/unloading supply of slings and movement of the machine at site shall be provided by Company, free of charge. However actual activities of loading/ unloading, internal shifting of machines shall have to be done by contractor's manpower.

HOUSEKEEPING

It is the responsibility of the contractor to ensure good housekeeping at work site. The scrap debris, unwanted material etc. shall be removed frequently from the work place to avoid accident and work area shall be kept tidy. Gangways shall be kept clear of obstructions. Contractor shall deploy dedicated personnel for housekeeping.

JOB COMPLETION TIME

The total contract duration is as specified in the contract. However for individual works from time to time as and when need arises, separate intimations shall be issued from individual plants/ EIC. Contractor shall ensure mobilization of all required resources and completion of the job including dismantling, etc. as per EIC

instructions.

1130	400038	Prov. & fixng 150 mm PVC water stopper	1	RM	Providing and fixing in position 150 mm wide caliplast 102 or approved quality PVC water stops for const.
------	--------	----------------------------------------	---	----	-----------------------------------------------------------------------------------------------------------

1140	400039	Making metal scaffolding with pipe	1	M3	SCAFFOLDING : Making scaffolding as per requirement and DFPCL's safety standard with contractors material (including pipes, scaffolding, clamp, bracings and binding materials and platforms with wooden planks) and fixing properly as per DFPCL' s safety standards for repair of RCC ceiling, beams, columns, walls etc. Payment shall be paid in m3 for any height with bottom of the scaffolding to be considered as the floor level.
1150	400190	P&F galvanised chain link 12 G.	1	M2	Providing & fixing galvanised chain link fencing made out of following gauge wire diamond square of 50mm thk on MS angles 65x65x6 with the help of flats of 25mm x 3mm chain link fencing shall be held tight by means of 3 horizontal wires of 4mm thk. MS angles, concrete for pedestals etc.shall be paid seperately as per structural steel rate and concrete rate. Steel ahall be supplied free of cost.
1160	400192	Supplying and fixing barbed wire fencing	1	RM	Supplying and fixing barbed wire fencing to the existing structural post of compound walls and concrete post including tighteneing with turn buckles, removal of damaged barbed wire and returning to Stores/scrapyard in proper bundles as directed.

1170	400505	p/f 100 mm pvc rain water pipe with fitt	1	M	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1) providing and fixing pvc rain water pipe 100mm dia. 2) item is including all fitting like hook . Clamp 3) item is including scaffolding and necessary arrangenent like safety net 4) item is applicable for all height <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water will be provided free of Cost for work inside DFPCL premises. 2) Issuing the permit after complete preparation by Contractor.
1180	400506	p/f 150 mm pvc rain water pipe with fitt	1	M	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1) providing and fixing pvc rain water pipe 150mm dia. 2) item is including all fitting like hook . Clamp 3) item is including scaffolding and necessary arrangenent like safety net 4) item is applicable for all height <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water will be provided free of Cost for work inside DFPCL premises. 2) Issuing the permit after complete preparation by Contractor.
1190	400583	P/A site mixed polymer modified c.m	1	M2	<p>Contractor's Scope :</p> <ol style="list-style-type: none"> 1) providing and applying polymer modified cement mortar in layer 2) Each layer not exceeding 20 mm thick up to 40 mm thick including toweling with wooden tools etc as specified applied while bond coat is still track 3) Item is measured on the basis of consumption of prepared mortar <p>DFPCL Scope :</p> <ol style="list-style-type: none"> 1) Electricity, water will be provided free of Cost for work inside DFPCL 2) Issuing the permit after complete preparation by Contractor.

1200	400429	Prov. false ceiling armstrong make	1	M2	<p>Contractor's Scope :</p> <p>1)Providing using Aluminium Frame Tees including all suspended arrangements</p> <p>2) Make to be Armstrong type perforated Sheets</p> <p>3) Work at all heights including scaffolding which will be non payable.</p> <p>4) Necessary permits to be taken & safety rules & regulations must be followed.</p> <p>DFPCL Scope :</p> <p>1) Electricity, water will be provided free of Cost for work inside DFPCL premises.</p> <p>2) Issuing the permit after complete preparation by Contractor.</p>
1210	400430	Removal of Old False Ceiling any make	1	M2	<p>Contractor's Scope :</p> <p>1)Removal of False Ceiling (Any Make)</p> <p>2) Shifting the debris out side DFPCL premises.</p> <p>3) Work at all heights including scaffolding which will be non payable.</p> <p>4) Shifting the scrap to scrap yard after taking SGM.</p> <p>5) Necessary permits to be taken & safety rules & regulations must be followed.</p> <p>DFPCL Scope :</p> <p>1) Electricity, water will be provided free of Cost for work inside DFPCL premises.</p> <p>2) Issuing the permit after complete preparation by Contractor.</p>
1220		P.& Fix.PVC Pipe 50 mm dia. Incl. fixtures	1	RM	
1230		P.& Fix.PVC Pipe 200 mm dia. Incl. fixtures	1	RM	
1240		Pr.& Lay Microconcreting using ready mix	1	M3	

Scaffolding/hydra/ Crane will be provided by DFPCL, wherever not mentioned in above scope.

The services of Fabricator, Welder, Rigger, and Helper which are mentioned in this tender shall be used for other services than the specifically mentioned in this tender.

Commercial Terms and Conditions:

1. Mobilization: Within 15 days from the date of receipt of PO/ email confirmation.
2. Payment Terms: Monthly one (Running Bill) Bill within 45 days which is to be certified by our job coordinator.
3. The contract is on value basis. The estimated value of contract will be approximately 1 Crores. It is proposed to engage 2/3- agencies to carry out the work.
4. The Contract will be awarded on L1 basis.
5. The L2 / L3 bidder has to match the L1 rates for each item for award of work to get share of business
6. The payment will be made through RTGS. The Bankers details to be provided by the bidder along with offer.
7. Validity of the contract: 2 Years from the date of receipt of PO-. The contract may be extended by another 3 months with the same rates if the contract value is not fully utilized. Even after extension of the contract if the value still not fully utilized then the contract will be terminated by DFPCL.
8. Taxes and Duties: Taxes and duties will be paid by DFPCL as per government notifications
9. Security Deposit: 10% of basic order value will be retained by DFPCL or equal amount of Bank Guarantee will be submitted by the contractor valid till the completion of the contract and certified by our technical team.
10. FORCE MAJEURE CONDITION:

The term force Majeure as employed herein shall mean acts of God, War, Revolt, Terrorist Act , Accident , Fire, Flood and Acts and Regulations of respective Governments, authorities.. Upon occurrence of such cause and upon its termination, the party alleging that it has been rendered unable as aforesaid thereby, shall notify the other party in writing within 72 hours, the full particulars and satisfactory evidence support of his claim. Time for purpose_ of the relative obligations suspended by the force majeure shall then stand extended by the period of delay, which is directly caused by force majeure event.

11) Jurisdiction :

The Court at Panvel, India only shall have Jurisdiction to deal with and decide any legal matter whatsoever arising out of this Tender order.

12) ARBITRATION :

All disputes or differences whatsoever arising, between the parties out of or relating to the supply or effect of this order or the breach thereof shall be referred to Sole Arbitration to be nominated by DFPCL & the Contractor/ Tenderer mutually in accordance with Arbitration and Conciliation Act, 1996, rules & amendments carried out from time to time. The award passed in pursuance thereof shall be binding on the parties. Arbitration sitting shall be at Mumbai/ Panvel and the proceedings shall be conducted in English. The cost of arbitration shall be shared equally by the parties.

13) Termination:

- A. The Contract/ Tender can be terminated by either party i.e. DFPCL or the Contractor/ Tenderer, after giving three (3) month's notice to the other party. However, DFPCL reserves the right to terminate the contract without giving any notice in case of the Contractor commits breach of any of the terms of the contract. DFPCL's decision in such a situation shall be final and binding on the Contractor/ Tenderer without any objection or resistance.
- B. On termination of the contract, the Contractor/ Tenderer will hand over all the equipment's/ furniture/ article etc. supplied by DFPCL (if any) in good working condition back to DFPCL except normal wear and tear.
- C. If the successful bidder/ Contractor withdraws or the services provided by the successful bidder are not found satisfactory (say in a month or so) during the probationary period of three months from the date of taking over charge /Job contract, DFPCL reserves the right to terminate the contract without giving any notice and initiate appropriate necessary action in the matter for making alternate arrangements. The Contractor shall continue till such time DFPCL finds alternative arrangement.
- D. In case it is found that any information furnished by the Tenderer/ Vendor/ Supplier is false or incorrect, the Company at its sole discretion may terminate the Contract/ Order without giving any notice. The Company shall reserve its right to seek appropriate damages from the Tenderer/ Vendor/ Supplier.
Any loss incurred by the Company in this respect will be on the Tenderrer/ Vendor/ Supplier.

14. Job Controller – Mr. Manish Pandit of DFPCL shall be the job controller.

15. The rates quoted by the Contractor shall remain firm till the completion of contract period and also during extended period if any. No escalation on any other ground shall be allowed.

(On Contractor's letterhead)

DETAILS OF BLACKLISTING / DISQUALIFICATION / FORFEITURE OF B.G. / S.D.

- 1) Whether your Firm/Company is blacklisted by DFPCL or any other Public Sector / Govt. / Quasi-Govt Organisation / any other client : **Yes / No**. If yes please mention details.
- 2) Whether your Contract was terminated before expiry of Contract period or Security Deposit / E.M.D forfeited by our Company or any other Public Sector/Govt./Quasi Govt Organization / Any other client : **Yes / No**. If yes please mention details.
- 3) Whether Proprietor/Partner/Director (as applicable) has been prosecuted by any judicial court for any criminal breach of trust : **Yes / No**. If yes please mention details.

(Signature of the Contractor & Seal)

(On Contractor's letterhead)

INFRASTRUCTURE / RESOURCES :

1. Total number of resources employed : _____
2. No. of branch offices : _____ (details of address, Telephone No., Fax No. etc.)
3. No. of FMS Contracts engaged in Mumbai with Avg value of Contract:

(Signature of the Contractor & Seal)

(On Contractor's letterhead)

GENERAL INFORMATION :

1. Name & address of the Tenderers Firm / Company : _____
2. Office Telephone No. : _____
3. Office Fax No. : _____
4. Year of Establishment : _____
5. Constitution of the Firm : Proprietorship/Partnership/ Pvt. Ltd./ Pub Ltd. Co./Co-operative .
6. Name, Address of Partner / Directors : _____
7. Name of contact person : _____
8. Telephone no. of contact person: Office _____
Residence _____
Mobile _____
9. Name & Designation of Authorised Signatory : _____
10. Details of sister concerns
 - a) Name & Address:
 - b) Activities engaged in by Sister Concern:
 - c) Names, Addresses & Telephone Nos. of Proprietors/Directors/Partners of Sister concerns.

(Signature of the Contractor & Seal)